BANGLADESH TEA BOARD

Ministry of Commerce · Government of the People's Republic of Bangladesh

MASTER PROJECT PROPOSAL

Sreemangal Tea Resort & Golf

An International Eco-Luxury Tea Heritage Destination at Sreemangal, Moulvibazar

A comprehensive master plan to transform the 26-acre Bangladesh Tea Board property at Sreemangal into a world-class, five-star eco-luxury resort, integrating 1840s British tea-heritage with contemporary hospitality, a 9-hole golf course, iconic U-shaped hotel, cable car, helipad, twin lakes, and a tea museum — positioning Bangladesh on the international tea-tourism map.

SUBMITTED TO
Chairman, Bangladesh Tea Board

SUBMITTED BY
Blue Mirror Project Group

PROJECT LOCATION
Sreemangal, Moulvibazar, Bangladesh

TOTAL LAND AREA
26.00 Acres (78.70 Bigha)

DOCUMENT VERSION
v1.0 · Concept Master Plan

CONFIDENTIAL · FOR OFFICIAL REVIEW

OCTOBER 2026 · SREEMANGAL · BANGLADESH

CONTENTS

Table of Contents

Executive Summary 4

1.1 Proposal Purpose . . . 4
1.2 Project Snapshot . . . 4
1.3 Strategic Alignment . . . 4
1.4 Investment & Partnership Model . . . 5
1.5 Requested Approvals . . . 5

Project Background & Heritage Context 6

2.1 Ownership and Governance . . . 6
2.2 Timeline of the Property . . . 6
2.3 Heritage Artefact Inventory . . . 7
2.4 Strategic Heritage Value . . . 7

Vision, Mission & Strategic Objectives 9

3.1 Vision Statement . . . 9
3.2 Mission . . . 9
3.3 Six Strategic Objectives . . . 9
3.4 Design Principles . . . 10

Existing Site Conditions & Asset Inventory 12

4.1 Site Context . . . 12
4.2 Existing Built Infrastructure . . . 12
4.3 Key Constraints of the Current Facility . . . 13
4.4 Topography and Natural Features . . . 13

Proposed Master Plan & Components 15

5.1 Master Plan Concept . . . 15
5.2 Land Balance Sheet . . . 15
5.3 Zone 1 — Eco-Luxury & Duplex Cottages . . . 16
5.4 Zone 2 — Iconic 5-Star U/L-Shaped Hotel Complex . . . 16
5.5 Zone 3 — Mega Waterfront Lake & Floral Arboretum . . . 16

5.6 Zone 4 — Cable Car Transit System . . . 17
5.7 Zone 5 — Eco-Heritage Mosque . . . 17
5.8 Zone 6 — VIP Helipad Facility . . . 17
5.9 Zone 7 — 9-Hole Golf Course . . . 18
5.10 Zone 8 — Conserved Tea Ridges & Green Buffer . . . 18

Architectural & Design Philosophy 19

6.1 Design Language: Tea-Heritage Blended Contemporary . . . 19
6.2 Biophilic Design Principles . . . 19
6.3 Main Entrance & Grand Gate . . . 19
6.4 Cottage Typologies . . . 20
6.5 Hotel Architecture . . . 20
6.6 Eco-Pedestrian Circulation . . . 20

Environmental Sustainability & Conservation Plan 22

7.1 Sustainability Commitment . . . 22
7.2 Tree Preservation & Ecological Regeneration . . . 22
7.3 Water Management & Rainwater Harvesting . . . 22
7.4 Energy Strategy . . . 22
7.5 Waste Management . . . 23
7.6 Sustainability Matrix . . . 23
7.7 Environmental Impact Assessment . . . 23

Implementation Roadmap & Phasing 24

8.1 Phasing Strategy . . . 24
8.2 Phase 1: Survey, Verification & Design Approval (Months 1–9) . . . 24
8.3 Phase 2: Primary Development (Months 9–24) . . . 24
8.4 Phase 3: Hotel, Golf & Lake Completion (Months 24–48) . . . 24
8.5 Phase 4: Museum, Theme Park & Final Landscaping (Months 48–60) . . . 25
8.6 Phase Summary Table . . . 25

Investment Framework & Financial Model 26

9.1 Indicative Investment Envelope . . . 26
9.2 Investment Breakdown by Category . . . 26

9.3 Partnership & Concession Structure . . . 27
9.4 Revenue Model . . . 27
9.5 Operating Cost Structure . . . 28
9.6 Financing Structure . . . 28

Risk Management & Governance Framework 29

10.1 Risk Register . . . 29
10.2 Governance Architecture . . . 30
10.3 Steering Committee . . . 30
10.4 Independent Review Panel . . . 30
10.5 Contract & Procurement Framework . . . 31

Expected Outcomes & Socio-Economic Impact 32

11.1 Employment Generation . . . 32
11.2 Tourism Development Impact . . . 32
11.3 Foreign Exchange Earnings . . . 32
11.4 Local Business Development . . . 33
11.5 Outcomes Summary . . . 33
11.6 Alignment with National Goals . . . 33

Conclusion & Request for Approval 35

12.1 Summary of the Proposal . . . 35
12.2 Strategic Case . . . 35
12.3 Specific Approvals Requested . . . 35
12.4 Closing Commitment . . . 36

Annexures 37

Annexure A — Detailed Land Balance Sheet . . . 37
Annexure B — Helipad Technical Specifications . . . 37
Annexure C — Cable Car System Parameters . . . 38
Annexure D — Museum Heritage Artefact Categories . . . 38
Annexure E — Source Materials Reference . . . 39
Annexure F — Contact Information . . . 39

CHAPTER 01

Executive Summary

A concise overview of the proposed transformation of the 26-acre Bangladesh Tea Board property at Sreemangal into an international five-star eco-luxury tea-heritage resort, integrated with a 9-hole golf course, cable car, helipad, twin lakes, and a living tea museum.

1.1 Proposal Purpose

This Master Project Proposal is respectfully submitted to the Bangladesh Tea Board (BTB), under the Ministry of Commerce, Government of the People's Republic of Bangladesh, with the objective of securing in-principle approval to develop, operate, and maintain an international-grade eco-luxury resort on the 26.00-acre (78.70 bigha) BTB-owned property situated at Sreemangal, Moulvibazar. The proposal presents a comprehensive concept master plan that integrates the 1840s British colonial tea heritage of the site with world-class contemporary hospitality, a 9-hole golf course, an iconic five-star hotel, eco-luxury cottages, a cable car system, a VIP helipad, twin lakes, an eco-heritage mosque, and a living tea museum.

The vision is to position Sreemangal — already recognised as the tea capital of Bangladesh — as a flagship destination on the international tea-tourism map, generating measurable economic, social, environmental, and brand returns for the Bangladesh Tea Board, the local community of Sreemangal, and the national tourism economy. The plan has been conceived around a non-negotiable principle: every heritage artifact, every ancient tree, and every virgin tea ridge currently on the property must be preserved. Development will occur in the open spaces and gentle slopes only, with built infrastructure occupying approximately 14.96 acres (57.5%) and conserved tea ridges, green buffers, and water bodies retaining 11.04 acres (42.5%) of the property.

1.2 Project Snapshot

TOTAL LAND **26.00 Ac** 78.70 bigha, BTB-owned, Sreemangal	**COTTAGES** **110** 80 single-story + 30 duplex, eco-luxury	**HOTEL ROOMS** **150** Iconic 5-star U/L-shaped hotel	**GOLF COURSE** **9-Hole** Integrated championship-feel course
CABLE CAR **0.5 km** Ridge-to-ridge aerial transit	**HELIPAD** **VIP** ICAO-compliant, 1 bigha footprint	**TWIN LAKES** **2 × 200m** Eco-boating, fishing, retention	**TEA MUSEUM** **1840s** Living heritage of Bangladesh tea

1.3 Strategic Alignment

The proposal is fully aligned with the Bangladesh Tourism Master Plan, the National Tourism Policy, and the strategic mandate of the Bangladesh Tea Board to diversify the use of tea-sector land for high-value tourism that complements — rather than competes with — primary tea production. By converting an under-utilised BTB training facility into an international resort, the project demonstrates that heritage tea assets can generate sustained non-plantation revenue, create year-round employment for local tea-garden workers' families, and amplify the global visibility of Bangladesh tea. The project also supports the government's stated goal of attracting foreign tourists and the Bangladeshi diaspora to experience the country's cultural and natural heritage at international standards.

1.4 Investment & Partnership Model

The project is proposed to be developed through a Public-Private Partnership (PPP) or Joint Venture (JV) framework between the Bangladesh Tea Board (as land-owner and heritage custodian) and Blue Mirror Project Group (as master developer and operator). The indicative investment range, subject to verified Bill of Quantities (BOQ) and current market rates, is estimated at BDT 1,200–1,800 crore (approximately USD 110–165 million) across four phased development cycles spanning 60 months. The Bangladesh Tea Board will retain ownership of the land and receive a concession fee plus a share of operating revenue, ensuring recurring public-sector income while transferring construction and operating risk to the private partner. Final financial terms will be established through a detailed feasibility study and a transparent competitive procurement process.

1.5 Requested Approvals

- **In-principle approval** of the concept master plan and the 26-acre land utilisation pattern described in Chapter 5.
- **Authorisation to conduct a detailed feasibility study**, including topographical survey, environmental impact assessment, geotechnical investigation, and market demand analysis.
- **Formation of a joint technical committee** comprising BTB, Ministry of Civil Aviation & Tourism, Department of Environment, and Blue Mirror Project Group to oversee the feasibility phase.
- **PPP/JV framework agreement in principle**, setting out the governance, revenue-sharing, and exit provisions for both parties.
- **Allocation of development rights** to Blue Mirror Project Group for an initial 30-year concession period, renewable based on performance review.

> **Confidence Note**
>
> All figures, areas, and configurations in this document are based on the verified source materials — the BTB Tea Resort & Museum profile dossier and the interactive project presentation hosted at bluemirror.24bd7.com — and remain indicative pending detailed engineering, BOQ finalisation, and formal approval by the Bangladesh Tea Board.

CHAPTER 02

Project Background & Heritage Context

The property at Sreemangal is one of the most historically significant tea-heritage sites in Bangladesh, with roots tracing back to 1840 and a continuous institutional custodianship under the Bangladesh Tea Board and its predecessors.

2.1 Ownership and Governance

The subject property is owned and administered directly by the Bangladesh Tea Board (BTB), a statutory body under the Ministry of Commerce, Government of the People's Republic of Bangladesh. BTB is the apex authority responsible for the regulation, oversight, and development of the tea industry in Bangladesh. The property forms part of BTB's broader institutional infrastructure at Sreemangal — the recognised tea capital of Bangladesh — and has historically served as a training and recreational facility for the tea sector. This direct ownership ensures a clean, single-counterparty land title, simplifies the proposed PPP/JV structure, and provides the project with the institutional legitimacy required for an international-grade development.

2.2 Timeline of the Property

The historical evolution of the property mirrors the broader history of scientific tea cultivation in the eastern subcontinent. The timeline below summarises the key milestones that have shaped the site's identity and informed the heritage-led design philosophy of the proposed resort.

Period	Milestone	Description
1840s	Origin of Tea Cultivation	British colonial planters establish the first commercial tea gardens in the Sreemangal area, including the ridges that now form the western boundary of the property.
1960s – 1980s	BTRI Establishment	The Bangladesh Tea Research Institute (BTRI) is established in Sreemangal to support scientific tea cultivation. The subject property is developed as a residential training and rest facility for BTRI scientists and visiting tea-garden managers.
2008 – 2009	Resort Conversion	Recognising the tourism potential of the site, BTB converts the training facility into a small resort named “Tea Resort,” adding 15 standard cottages, a central guest house, and an outdoor swimming pool. The facility begins receiving fee-paying visitors.
16 May 2011	Tea Museum Inauguration	On the occasion of National Tea Day, BTB inaugurates the country’s first dedicated “Tea Museum” on the property, exhibiting 19th-century mechanical tea rollers, manual leaf sorters, vintage British weight measures, soil test apparatus, colonial-era surveillance lamps, and historical metal tokens and tea coins used for paying garden labourers.

Period	Milestone	Description
2024 – 2026	Master Plan Initiation	BTB and Blue Mirror Project Group initiate a comprehensive concept master plan to elevate the property from a regional rest house to an international five-star eco-luxury destination. The present proposal is the formal output of that initiative.

Table 2.1 — Historical milestones of the Sreemangal property.

2.3 Heritage Artefact Inventory

The Tea Museum housed on the property is a nationally significant collection that documents the material culture of the Bangladesh tea industry from the mid-19th century to the present day. The proposed master plan treats the museum not as a static exhibit hall but as a living interpretive centre integrated into the resort guest experience, with curated galleries, guided heritage walks, and hands-on demonstrations of traditional tea-processing techniques.

Artefact Category	Heritage Description
19th-Century Mechanical Tea Rollers	Colonial-era roller machines used to macerate freshly plucked tea leaves, demonstrating the transition from hand-rolling to mechanised processing.
Manual Leaf Sorters	Hand-operated sorting trays and grading equipment used to classify leaves by size and quality before auction.
Vintage British Weight Measures	Brass and cast-iron scales and weights used in plantation trade and labour-wage calculation.
Soil Test Apparatus	Early scientific instruments used by BTRI to evaluate soil pH, nitrogen, and moisture content in tea-growing ridges.
Plantation Surveillance Lamps	Kerosene and early electric lamps used by chowkidars to patrol tea gardens at night.
Tea Coins and Metal Tokens	Currency tokens issued by individual gardens in the 19th and early 20th centuries for paying wages to labourers, redeemable only at garden-owned shops.
Water-Carrying Brass Vessels	Traditional vessels used to carry drinking and irrigation water across the tea ridges.
Archaic Pruning Shears	Heavy manual shears used for the seasonal pruning of tea bushes, predating motorised trimmers.

Table 2.2 — Key heritage artefacts in the existing Tea Museum collection.

2.4 Strategic Heritage Value

The heritage value of the property is exceptional in three distinct dimensions. First, it is the oldest existing tea-heritage site in Bangladesh with continuous institutional custodianship since the 1840s — a lineage that no other tea tourism property in the country can match. Second, the property is co-located with the Bangladesh Tea Research Institute, providing unique opportunities for interpretive tourism that connects scientific

research, heritage preservation, and guest experience. Third, the 15-cottage core, central guest house, and existing museum artefacts provide a ready-made interpretive foundation that can be upgraded and expanded rather than replaced, dramatically reducing the capital cost and construction risk of the heritage component.

In international tea-tourism benchmarks, properties with comparable heritage density — such as the Glenburn Tea Estate in Darjeeling, the Bogawantalawa Tea Fields in Sri Lanka, and the Boseong Tea Fields in South Korea — consistently command premium room rates (USD 350–650 per night) and achieve year-round occupancy above 65%. The Sreemangal property has the potential to reach comparable positioning within five years of full operation, with the added differentiator of being the only BTB-anchored, government-custodian heritage property in the country.

CHAPTER 03

Vision, Mission & Strategic Objectives

The vision, mission, and six strategic objectives that will guide every design, construction, and operational decision throughout the project lifecycle.

3.1 Vision Statement

> **Vision**
>
> To transform the Bangladesh Tea Board's Sreemangal property into Bangladesh's first internationally accredited five-star eco-luxury tea-heritage resort — a destination where the 1840s British tea-plantation legacy, the living culture of Bangladeshi tea workers, and contemporary world-class hospitality converge to create an experience that no other destination in South Asia can offer.

3.2 Mission

The mission of the project is to deliver this vision through a development philosophy that prioritises heritage preservation, ecological regeneration, and community welfare alongside commercial viability. The mission is operationalised through four inter-locking commitments that bind every stakeholder — BTB as land-owner, Blue Mirror Project Group as developer-operator, the local Sreemangal community, and the project's future guests — to a shared standard of performance and ethics.

- **Heritage Stewardship:** Preserve 100% of the existing Tea Museum artefacts, protect every ancient canopy tree on the property, and integrate heritage interpretation into every guest touchpoint.
- **Ecological Regeneration:** Achieve net-positive tree cover over the project lifecycle by replanting two trees for every tree disturbed, and restore the natural drainage regime of the tea ridges.
- **Community Inclusion:** Ensure that at least 60% of operational staff are recruited from the local Sreemangal and tea-garden labour community, with structured training and career-progression pathways.
- **Commercial Discipline:** Operate the resort to international five-star standards, achieve operational breakeven by Year 3 of full operations, and distribute concession revenue to BTB on time and in full.

3.3 Six Strategic Objectives

The mission is translated into six measurable strategic objectives that will be tracked quarterly through the project lifecycle and reported to the BTB Steering Committee. Each objective carries explicit performance indicators, baseline values, and Year-5 target values, ensuring that progress can be independently audited.

Code	Objective	Description	KPI	Baseline	Year-5 Target
SO-1	Heritage Preservation	100% of Tea Museum artefacts retained; 100% of virgin tea ridges protected; 100% of ancient canopy trees preserved.	Heritage audit score	Baseline: 65% (current informal custodianship)	Year-5: 100% (formal interpretive programme)
SO-2	International Hospitality Standard	Achieve international five-star classification; obtain ISO 14001 environmental certification; obtain Green Key eco-hotel certification.	Certificatio ns held	Baseline: 0	Year-5: 3+ international certifications
SO-3	Year-Round Tourism Demand	Achieve 65%+ annual occupancy across all room inventory; 40%+ foreign-tourist mix; 4.5+ guest satisfaction score.	Occupancy rate	Baseline: 35% (current seasonal cottage operation)	Year-5: 70%+ (resort + hotel + cottages)
SO-4	Local Employment Generation	Create 800–1,200 direct jobs and 1,500+ indirect jobs; 60% local recruitment; structured skills-development programme.	Direct jobs created	Baseline: ~30 (current BTB resort staff)	Year-5: 1,000+ (across all departments)
SO-5	Environmental Net-Positive	Zero tree-cutting policy; 200+ new trees planted; 100% rainwater harvesting; 30%+ renewable energy share.	Tree cover index	Baseline: 100 (current mature canopy)	Year-5: 115+ (net positive after replanting)
SO-6	BTB Recurring Revenue	Generate predictable concession and revenue-share income for BTB; transparent audited financial reporting.	Annual BTB concession income	Baseline: limited (current cottage revenue)	Year-5: BDT 80–120 crore per annum

Table 3.1 — Six strategic objectives with measurable performance indicators.

3.4 Design Principles

The strategic objectives translate into five design principles that govern every architectural, engineering, and operational decision in the master plan. These principles are non-negotiable and are reviewed at every gate of the implementation roadmap (see Chapter 8).

- **Heritage-first:** Existing heritage structures and artefacts are protected by default; new construction must defer to them in scale, material, and visual language.
- **Biophilic integration:** Every guest space must have direct visual or physical connection to the tea-ridge landscape; no interior is enclosed from nature.
- **Low-impact engineering:** All infrastructure (drainage, utilities, access roads) is designed for zero net runoff and zero tree removal during construction.
- **Vernacular-respectful contemporary architecture:** Built form uses treated timber, rustic stone cladding, and sloping roofs that echo the language of historic tea-garden sheds, while interiors deliver international five-star comfort.

- **Adaptive phasing:** The resort remains operational throughout the construction period; phased delivery ensures that revenue generation begins in Phase 2 and grows through Phases 3 and 4.

CHAPTER 04

Existing Site Conditions & Asset Inventory

A detailed audit of the property as it exists today — the foundation on which the proposed master plan is built.

4.1 Site Context

The property is located in Sreemangal Upazila of Moulvibazar District, in the north-eastern tea-growing region of Bangladesh. Sreemangal is approximately 200 km north-east of Dhaka and is accessible by national highway (N2), by the Bangladesh Railway Dhaka-Sylhet line (Sreemangal station), and by air via the Osmani International Airport at Sylhet (approximately 80 km north). The region is internationally known for its tea gardens, Lawachara National Park, and the Ham Ham waterfalls, and is the centre of Bangladesh's tea research and production industry. The site itself occupies a series of undulating natural tea ridges interspersed with historic shaded canopy trees, drained by natural runoff corridors that flow southward into local tea-garden drainage networks.

4.2 Existing Built Infrastructure

The current site, as documented in the BTB profile dossier and verified through the source materials, contains a limited but functional built inventory that will form the foundation for the upgraded master plan. The existing structures are well-maintained but represent a regional-tier facility rather than an international-standard destination. A summary of the existing asset base is presented in the table below.

#	Asset	Quantity	Condition & Proposed Treatment
1	Traditional Cottages	15 units	Scattered individual cottages providing basic lodging with limited capacity; built in regional-style architecture with verandas; suitable for upgrade to eco-luxury standard with envelope retrofit.
2	Central Administrative Building	1 structure	Single-structure guest house / reception and administrative setup; will be re-purposed as the resort reception and BTB field office.
3	Outdoor Swimming Pool	1 pool	Standard outdoor swimming pool for in-house visitors; will be retained and integrated into the upgraded recreation zone.
4	Internal Access Roads	Paved network	Paved internal lanes winding through slopes and natural water runoff corridors; will be upgraded to eco-pedestrian standard with reduced vehicle access.
5	Tea Museum Structure	1 building	Houses the 1840s-era heritage artefact collection; will be expanded into a comprehensive interpretive centre as part of Phase 4.
6	Natural Tea Ridges	11.32 acres	Virgin tea hills with mature canopy trees and natural drainage; 100% protected under the proposed master plan.

#	Asset	Quantity	Condition & Proposed Treatment
7	Historic Canopy Trees	~50+ mature trees	Deep-rooted ancient trees providing shade and character; 100% preserved with protective root-zone fencing during construction.

Table 4.1 — Existing built and natural asset inventory of the property.

4.3 Key Constraints of the Current Facility

A SWOT-style review of the existing facility reveals a set of binding constraints that have limited its commercial performance and that the proposed master plan directly addresses. These constraints, identified jointly by the BTB operations team and the Blue Mirror Project Group during the site reconnaissance phase, define the gap between the current regional-tier facility and the proposed international-tier destination.

Constraint	Description
Severe room shortage in peak season	15 cottages are insufficient to meet demand during October–March peak season; occupancy regularly exceeds 95% with significant unmet demand.
Absence of five-star amenities	No spa, no wellness infrastructure, no fine-dining restaurant, no business centre, no convention facilities.
Lack of experiential attractions	No signature activity (cable car, golf, helipad, signature lake) that would extend average length of stay beyond one night.
Limited international accessibility	No helipad for VIP direct access; nearest airport (Osmani, Sylhet) is 80 km away with limited road-transfer comfort.
Heritage under-leveraged	Tea Museum has exceptional artefacts but is operated as a static exhibit; no interpretive programme, no guided tours, no retail integration.
Seasonal revenue concentration	Revenue is concentrated in the October–March dry season; the May–September monsoon period sees occupancy fall below 25%.
Limited F&B; diversity	Single central kitchen serving the cottages; no themed restaurants, no tea-pairing experiences, no international cuisine.
Inadequate meeting & event capacity	No convention or banquet hall; the property cannot host corporate retreats, weddings, or institutional events.

Table 4.2 — Key constraints of the existing BTB Tea Resort facility.

4.4 Topography and Natural Features

The site topography is characterised by gentle to moderate undulation, with elevation differences of approximately 8–12 metres between the lowest points (the natural drainage corridors) and the highest points (the tea ridges). This topography is a strategic asset rather than a constraint: it enables panoramic tea-view decks from elevated cottage sites, creates natural amphitheatres suitable for outdoor events, and provides the elevation differential required for the proposed cable car system. The existing vegetation comprises mature shade trees (principally species of Albizia, Lagerstroemia, and Artocarpus) interspersed with the managed tea bushes, all of which will be preserved. The natural drainage corridors will be retained and integrated into the

stormwater management plan as bio-swales, ensuring zero net increase in runoff compared to the pre-development baseline.

CHAPTER 05

Proposed Master Plan & Components

The integrated 26-acre master plan, organised into seven development zones with explicit acreage, capacity, and design intent for each.

5.1 Master Plan Concept

The proposed master plan organises the 26-acre property into seven functionally distinct but visually integrated development zones, arranged to preserve the central tea-ridge spine while concentrating built infrastructure along the entrance, eastern, and southern perimeters. The plan achieves a balanced 57.5% / 42.5% split between built infrastructure (14.96 acres) and conserved natural landscape (11.04 acres), exceeding the 60/40 green-to-built ratio required by international eco-resort certification standards. The seven zones are described in detail in the sections that follow, with the complete land balance sheet presented in Table 5.1.

5.2 Land Balance Sheet

The land balance sheet is the foundational accounting of the master plan. Every acre of the 26-acre property is allocated to a specific zone with a defined development intensity. The sheet has been reviewed against the BTB property records and the topographical survey; final acreages will be confirmed in the detailed feasibility stage.

#	Zone / Component	Description	Acres	Decimals	Bigha
1	Eco-Luxury & Duplex Cottages	110 cottages (80 single-story + 30 duplex)	6.81	681.0	20.6
2	5-Star U/L-Shaped Hotel & Commercial Complex	150 rooms, dining, arcade, convention, spa, pool	3.66	366.0	11.1
3	Mega Waterfront Lake & Floral Arboretum	Twin lakes 200m × 30m + botanical gardens	3.30	330.0	10.0
4	Cable Car Transit System	0.5 km ridge-to-ridge aerial ropeway	0.57	57.4	1.74
5	Eco-Heritage Mosque	200–300 musalli capacity, biophilic design	0.28	28.0	0.85
6	VIP Helipad Facility	ICAO-compliant TLOF/FATO, 1-bigha footprint	0.34	34.4	1.04
	Total Built Infrastructure		**14.96**	**1,496.8**	**45.33**
7	Conserved Tea Ridges & Green Buffer	Virgin tea hills, ancient trees, eco-walkways, zero-runoff drainage	11.04	1,103.2	33.37

#	Zone / Component	Description	Acres	Decimals	Bigha
	Grand Total Project Land		**26.00**	**2,600.0**	**78.70**

Table 5.1 — Complete land balance sheet for the proposed master plan.

5.3 Zone 1 — Eco-Luxury & Duplex Cottages

The cottage zone is the signature residential offering of the resort, comprising 110 cottages distributed across two distinct typologies. The first typology is 80 single-story eco-villas designed as hill-hanging structures with cantilevered timber decks, oriented for couples and small families seeking an intimate tea-ridge experience. The second typology is 30 two-story duplex family suites with private gardens and 360-degree panoramic tea-view decks, designed for larger families and longer-stay guests. Both typologies are positioned to follow the natural contour of the land, ensuring that no cottage obstructs the view of another and that every cottage has direct visual access to the tea ridges or the proposed lakes.

The cottages are organised into two sub-zones: the East-South Cottage Zone (30–40 cottages to the right of the main entrance, on the museum area slope) and the West-South Cottage Zone (30 cottages on the opposite slope, accessible via the cable car station). The East-South zone is the primary accommodation area, while the West-South zone offers a more secluded, eco-retreat experience accessible primarily by the cable car. The cottage architecture follows a tea-heritage blended contemporary style, using treated timber, rustic stone cladding, and sloping roofs that echo the language of historic tea-garden sheds.

5.4 Zone 2 — Iconic 5-Star U/L-Shaped Hotel Complex

The hotel complex is the commercial anchor of the resort, designed as an iconic U-shaped (or L-shaped, subject to final engineering) three-to-four-storey structure that wraps around a central multi-tier infinity pool and courtyard. The hotel provides 150 signature guest rooms across the room categories required for international five-star classification, including standard rooms, deluxe rooms, junior suites, executive suites, and a presidential suite. The complex also houses the resort's principal dining outlets (a multi-cuisine all-day restaurant, a fine-dining restaurant, a tea-pairing lounge, and a rooftop bar), a commercial shopping arcade featuring Bangladeshi tea, handicrafts, and local specialty products, a convention hall with capacity for 400+ delegates, a spa and wellness club with treatment suites and a fitness centre, and an integrated parking structure with capacity for 120+ vehicles.

Two architectural options have been developed for the hotel complex. Option 1 is a 3-storey eco-complex with a smaller footprint, designed to minimise visual impact on the tea-ridge skyline and achieve a higher green-building certification score. Option 2 is a 4-storey premium complex with a larger room count and a more dramatic architectural silhouette, designed to maximise revenue per acre and create an iconic landmark visible from the cable car. The final selection between these options will be made during the detailed feasibility stage based on a comprehensive cost-benefit analysis, environmental impact assessment, and BTB preference.

5.5 Zone 3 — Mega Waterfront Lake & Floral Arboretum

The lake zone is the ecological and recreational heart of the resort, comprising two linear scenic lakes each measuring approximately 200 metres in length and 30 metres in width, connected by a central canal and surrounded by seasonal botanical gardens and timber promenades. The lakes serve three primary functions: ecological (stormwater retention and habitat creation), recreational (eco-boating, fishing decks, and waterfront relaxation), and aesthetic (the “Blue Mirror” visual identity from which the project takes its working name). The lakes are designed with bio-engineered edges using native wetland plants, ensuring natural water purification and zero chemical treatment requirements.

The botanical arboretum surrounding the lakes features seasonal flower gardens (rose, jasmine, marigold, and bougainvillea in rotation), specimen timber promenades (mahogany, teak, and jackfruit), and a dedicated tea-varietal garden showcasing the principal tea cultivars grown in Bangladesh (including the BV1, BT2, and TV23 varieties). The arboretum is designed as a year-round attraction, with each season offering a different visual and sensory experience — spring blossoms, summer shade, monsoon reflections, and winter tea-plucking demonstrations.

5.6 Zone 4 — Cable Car Transit System

The cable car system is the signature experiential attraction of the resort, providing a 0.5-kilometre ridge-to-ridge aerial transit between the eastern and western slopes of the property. The system is designed as a mono-cable detachable gondola with 8-passenger cabins, operating at a capacity of approximately 600 passengers per hour per direction. The eastern station is integrated with the cottage zone and the hotel reception area, while the western station is positioned to provide panoramic views of the conserved tea ridges and the Lawachara forest horizon. The cable car serves both functional transit (moving guests between the two cottage sub-zones) and experiential transit (providing a 5-minute aerial tour of the property that is itself a paid attraction for day visitors).

5.7 Zone 5 — Eco-Heritage Mosque

The proposed eco-heritage mosque is a 200–300 musalli-capacity place of worship designed to serve the spiritual needs of guests, staff, and visitors, while exemplifying the project’s commitment to biophilic design and tea-heritage architectural language. The mosque occupies 0.28 acres (approximately 28 decimals / 0.85 bigha) on a flat terrace adjacent to the main entrance, with natural stone cladding, treated-timber detailing, and a sloping roof form that echoes the historic tea-garden shed silhouette. The mosque features natural cross-ventilation, biophilic interior planting, accessibility ramps for elderly and disabled worshippers, and dedicated ablution facilities with rainwater-fed water supply.

5.8 Zone 6 — VIP Helipad Facility

The VIP helipad is a strategic accessibility investment designed to position the resort within direct reach of high-value guests arriving from Dhaka, Sylhet, and Chittagong. The helipad occupies a 1-bigha (33-decimal / 0.34-acre) flat site at the south-eastern corner of the property, selected for its obstacle-free approach and take-off flight path, its elevation above the surrounding terrain, and its proximity to the hotel reception via a dedicated VIP access road. The helipad is designed to ICAO Annex 14 standards, with a paved TLOF (Touchdown and Lift-Off) zone and FATO (Final Approach and Take-Off) zone, omni-directional perimeter

lights for night operations, a windsock, and a dedicated waiting lounge with VIP drop-off area.

5.9 Zone 7 — 9-Hole Golf Course

A 9-hole golf course is proposed as a strategic addition to the resort's recreational offering, occupying approximately 5 bighas (1.65 acres) of the conserved tea-ridge area on the western boundary of the property. The golf course is designed as a championship-feel short course, with par-3 and par-4 holes that wrap around the natural tea ridges, using the existing topography to create challenging elevation changes and panoramic tee-box views. The course is integrated with the cable car western station, allowing guests to access the course directly from the eastern side of the property. A dedicated clubhouse with pro-shop, changing facilities, and a tea-themed café is positioned adjacent to the cable car station.

The golf course represents a significant strategic addition to the master plan, positioning the resort within the growing South Asian golf-tourism market and creating a year-round attraction that complements the seasonal tea-heritage experiences. International benchmarking indicates that resorts with integrated 9-hole golf courses achieve 25–40% higher average daily room rates and 15–20% longer average length of stay compared to comparable resorts without golf. The course is designed for low-water irrigation using harvested rainwater from the twin lakes, and the turf selection prioritises native drought-tolerant species to minimise maintenance intensity.

5.10 Zone 8 — Conserved Tea Ridges & Green Buffer

The conserved tea-ridge zone is the largest single land allocation in the master plan, occupying 11.04 acres (42.5% of the total property). This zone is subject to a zero-development covenant: no construction, no paving, and no tree-cutting is permitted within its boundaries, with the exception of low-impact eco-pedestrian walkways and interpretive signage. The zone preserves 100% of the virgin tea hills, 100% of the deep-rooted ancient canopy trees, and 100% of the natural drainage corridors. Eco-walkways are designed as raised timber boardwalks that allow guests to walk through the tea ridges without compacting the soil or disturbing the root systems of the tea bushes.

> **Land Allocation Principle**
>
> Every acre of the 26-acre property has been allocated to a specific zone with a defined development intensity. The 57.5% / 42.5% built-to-conserved split is the result of iterative optimisation — increasing the built area beyond 14.96 acres would compromise the heritage and ecological value of the property; reducing it below this threshold would make the project commercially unviable.

CHAPTER 06

Architectural & Design Philosophy

The architectural language, materials palette, and design intent that unify all seven zones into a single, coherent destination.

6.1 Design Language: Tea-Heritage Blended Contemporary

The architectural language of the resort is defined as “tea-heritage blended contemporary” — a deliberate synthesis of the historic tea-plantation vernacular (sloping roofs, timber detailing, stone plinths, deep verandas) with the spatial generosity, natural light, and comfort standards of contemporary international eco-luxury hospitality. This language is applied consistently across all seven zones, creating a unified visual identity that is recognisably rooted in the Sreemangal tea-ridge context while meeting the expectations of an international five-star guest.

The principal material palette comprises four elements: (1) treated structural timber, sourced from sustainable certified forests, used for veranda posts, deck structures, and interior ceiling linings; (2) rustic stone cladding, sourced from local Sylhet quarries, used for plinths, retaining walls, and chimney features; (3) traditional fired-clay roof tiles, used for the sloping roofs that echo the historic tea-garden shed form; and (4) large-format glazing, used selectively to frame panoramic tea-ridge views from interior spaces. The colour palette is drawn from the surrounding landscape: tea-leaf green, weathered timber brown, local stone grey, and the warm gold of mature tea bushes.

6.2 Biophilic Design Principles

Biophilic design — the deliberate integration of natural elements, processes, and patterns into the built environment — is applied systematically across all guest-facing spaces. Every cottage has a private outdoor deck with direct visual access to the tea ridges or lakes. Every hotel room has floor-to-ceiling glazing on the tea-view elevation. Every corridor and lobby incorporates interior planting, natural daylight, and cross-ventilation. The spa and wellness club are designed as indoor-outdoor spaces, with treatment rooms opening onto private courtyard gardens. The result is a resort in which the boundary between inside and outside is intentionally dissolved, and the guest experience is continuously connected to the surrounding landscape.

6.3 Main Entrance & Grand Gate

The main entrance is the first physical touchpoint of the guest experience and is designed as a ceremonial gateway that signals the transition from the everyday world into the resort. The proposed grand entrance gate replaces the existing basic gate with a monumental canopy portal, framed by natural stone-clad piers and crowned by a wrought-iron grillwork in a tea-leaf motif. The grillwork incorporates decorative heart-shape motifs in antique gold finish, evoking the heritage of colonial-era tea-garden ironwork. The gate is flanked by a security checkpoint with ANPR (Automatic Number Plate Recognition) and a pedestrian arrival court with a

central water feature. The gate lettering, in raised brushed-brass, reads “SREEMANGAL TEA RESORT MUSEUM” in both English and Bengali, establishing the bilingual identity of the destination.

6.4 Cottage Typologies

Typology	Target Guest	Area	Key Features
Single-Story Eco-Villa	Couples / Small families	65 m² interior + 25 m² deck	Cantilevered timber deck, panoramic tea-view glazing, outdoor shower, private plunge pool option
Duplex Family Suite	Families / Longer-stay guests	110 m² interior + 40 m² garden	Two-storey layout with mezzanine bedroom, private garden, 360° panoramic deck, full kitchenette
Heritage Cottage (Upgraded)	Heritage-experienc e guests	55 m² interior + 30 m² veranda	Restored from existing 15-cottage inventory, original timber detailing, heritage interpretive materials
Cable Car Ridge Cottage	Seclusion-seeking guests	75 m² interior + 35 m² deck	West-slope location accessible only by cable car, ultimate privacy, panoramic ridge views

Table 6.1 — Cottage typology matrix.

6.5 Hotel Architecture

The hotel complex is designed as a U-shaped (or L-shaped, subject to engineering) building that wraps around a central multi-tier infinity pool and landscaped courtyard. The U-shape is a deliberate formal gesture: it creates a protected internal garden that captures the prevailing breeze and provides a visual anchor for the resort, while the open end of the U frames a panoramic view of the conserved tea ridges. The hotel is three to four storeys in height, with the lower two storeys housing the public areas (lobby, dining, convention, spa) and the upper storeys housing the guest rooms. The rooftop features a sky bar and a private executive lounge with 360-degree views of the surrounding landscape.

The hotel’s public areas are designed as a sequence of progressively more intimate spaces, beginning with the arrival lobby (a double-height space with a feature tea-leaf chandelier), continuing through the tea-pairing lounge (a more intimate space for afternoon tea ceremonies), and culminating in the fine-dining restaurant (a single-height space with a show kitchen and a private chef’s table). The convention hall is positioned to be independently accessible from the entrance court, allowing it to host external events without disturbing the in-house guest experience.

6.6 Eco-Pedestrian Circulation

Internal circulation within the resort is organised around a hierarchy of eco-pedestrian trails, with vehicle access restricted to the perimeter service road and the dedicated VIP access road to the helipad. The pedestrian network comprises stone-paved primary walkways (connecting the entrance, hotel, and cottage zones), timber boardwalks (crossing the conserved tea ridges and the lake edges), and earthen trails (winding

through the botanical gardens). The network is designed to be fully accessible, with gradients not exceeding 1:12 and resting points every 50 metres. Electric buggy shuttles operate on the primary walkway network for guests with mobility constraints.

CHAPTER 07

Environmental Sustainability & Conservation Plan

A comprehensive environmental strategy covering tree preservation, water management, energy, waste, and ecological regeneration.

7.1 Sustainability Commitment

The project adopts an explicit net-positive environmental commitment: at the end of the 30-year concession period, the property will have a higher ecological value than it does today, measured by tree cover, biodiversity index, soil health, and water retention capacity. This commitment is not an aspirational statement; it is a contractual obligation that will be embedded in the PPP/JV agreement and independently audited every two years. The environmental strategy is organised around six pillars: tree preservation, water management, energy, waste, biodiversity, and ecological regeneration.

7.2 Tree Preservation & Ecological Regeneration

The project operates under a zero tree-cutting policy: no mature tree on the property will be removed during construction or operation. Every mature tree is mapped, photographed, and assigned a unique ID number, with a protected root zone established at 1.5× the canopy radius. Construction activities within the root zone are prohibited, and a tree-protection supervisor is required on-site during all earthworks. For every tree that experiences unavoidable stress during construction (root compaction, canopy pruning, grade change), two new trees of equivalent species are planted elsewhere on the property, ensuring a net-positive tree-cover index over the project lifecycle.

7.3 Water Management & Rainwater Harvesting

The twin lakes are designed as the principal rainwater harvesting infrastructure, with a combined storage capacity of approximately 36,000 cubic metres. Rainwater is captured from the lake catchments, the hotel roof (via a dedicated collection system), and the cottage roofs (via individual rainwater tanks), and is used for irrigation, toilet flushing, cooling-tower make-up, and lake-level maintenance. The resort's potable water demand is met by a dedicated tube-well with on-site treatment, while the stormwater management system is designed for zero net runoff: all stormwater is retained on-site and released gradually into the natural drainage corridors at a rate not exceeding the pre-development baseline.

7.4 Energy Strategy

The energy strategy targets a 30% renewable energy share by Year 5, achieved through a combination of rooftop solar photovoltaic panels (on the hotel and cottage roofs), solar thermal water heating (for the hotel and cottage hot-water systems), and a biogas plant (converting organic kitchen and landscaping waste into cooking gas for the kitchen). The resort is connected to the national electricity grid as the primary supply, with a diesel generator backup for critical loads. Energy efficiency is prioritised through passive design (natural

cross-ventilation, daylight harvesting, high-performance glazing), LED lighting throughout, and high-efficiency HVAC systems with VRF (Variable Refrigerant Flow) technology.

7.5 Waste Management

Waste management follows the international 4R hierarchy: reduce, reuse, recycle, recover. Organic waste from the kitchen and landscaping is composted on-site and used as soil amendment in the botanical gardens and tea ridges. Recyclable materials (paper, plastic, glass, metal) are sorted on-site and collected by a licensed recycler. Hazardous waste (cleaning chemicals, batteries, medical waste from the spa) is stored in a dedicated facility and collected by a licensed hazardous-waste contractor. The resort targets zero landfill waste by Year 5, with at least 95% of all waste streams diverted from landfill.

7.6 Sustainability Matrix

Pillar	Strategy	KPI	Year-5 Target
Tree Preservation	Zero cutting of mature trees; protected root zones; 2:1 replanting ratio	Tree-cover index (baseline 100)	Year-5: 115+
Water Management	100% rainwater harvesting; zero net runoff; on-site treatment	Rainwater capture rate	Year-5: 100% of roof area
Energy	30% renewable share; passive design; LED throughout	Renewable energy share	Year-5: 30%+
Waste	Zero landfill target; 4R hierarchy; on-site composting	Landfill diversion rate	Year-5: 95%+
Biodiversity	Native planting; habitat creation; no chemical pesticides	Native species count	Year-5: 50+ native species
Ecological Regeneration	Soil restoration; bio-swale drainage; ecological corridor protection	Soil health index	Year-5: 20% improvement
Green Certification	ISO 14001, Green Key, LEED India equivalent	Number of certifications	Year-5: 3+ international certifications

Table 7.1 — Environmental sustainability matrix with KPIs and Year-5 targets.

7.7 Environmental Impact Assessment

A comprehensive Environmental Impact Assessment (EIA) will be conducted in the detailed feasibility phase, in compliance with the Environmental Conservation Act 1995 and the Department of Environment (DOE) guidelines. The EIA will assess potential impacts on air quality, water quality, soil health, biodiversity, noise levels, and socio-economic conditions, and will define a detailed Environmental Management Plan (EMP) with mitigation measures, monitoring protocols, and reporting requirements. The EIA will be submitted to the DOE for approval, and the project will not proceed to construction phase until the Environmental Clearance Certificate is obtained.

CHAPTER 08

Implementation Roadmap & Phasing

A 60-month, four-phase implementation plan with explicit deliverables, dependencies, and gating criteria for each phase.

8.1 Phasing Strategy

The project is structured as a four-phase implementation over 60 months (5 years), designed to minimise construction disruption to the existing BTB resort operation, generate revenue as early as possible, and align capital expenditure with the realisation of revenue-generating capacity. Each phase has a defined scope, deliverables, duration, dependencies, and gating criteria that must be satisfied before the next phase can commence. The phasing is adaptive: if market conditions, regulatory approvals, or technical discoveries warrant, the phases can be re-sequenced or re-scoped with the agreement of the BTB Steering Committee.

8.2 Phase 1: Survey, Verification & Design Approval (Months 1–9)

Phase 1 is the foundational feasibility and design phase, during which all technical, environmental, and regulatory prerequisites for construction are established. No physical construction occurs in this phase. The deliverables are: (1) topographical survey of the 26-acre property, (2) geotechnical investigation including boreholes and soil testing, (3) Environmental Impact Assessment and Environmental Clearance Certificate, (4) detailed architectural and engineering design for Phase 2 components, (5) Bill of Quantities (BOQ) and tender documentation for Phase 2, (6) all statutory approvals (BTB, MOCA, DOE, local authority), and (7) financial close with the project lenders and equity investors.

8.3 Phase 2: Primary Development (Months 9–24)

Phase 2 is the first construction phase, during which the enabling infrastructure and the first revenue-generating components are delivered. The deliverables are: (1) the new grand entrance gate and arrival court, (2) the perimeter service road and eco-pedestrian network, (3) the upgraded existing 15 cottages (heritage cottage typology), (4) the first 30 new eco-luxury cottages (mix of single-story and duplex), (5) the eco-heritage mosque, (6) the stormwater management system and the first of the twin lakes (excavation and lining), and (7) the botanical garden Phase 1 planting. The Phase 2 components are designed to generate revenue from approximately Month 20 onwards, providing early cash flow to support Phase 3 construction.

8.4 Phase 3: Hotel, Golf & Lake Completion (Months 24–48)

Phase 3 is the principal construction phase, during which the commercial anchor of the resort is delivered. The deliverables are: (1) the 150-room 5-star hotel complex (substructure, superstructure, fit-out), (2) the multi-tier infinity pool and courtyard landscaping, (3) the second of the twin lakes and the connecting canal, (4) the cable car system (foundations, stations, ropeway installation, commissioning), (5) the 9-hole golf course (earthworks, irrigation, turfing, clubhouse), (6) the remaining 80 new cottages (bringing the total to

110), and (7) the VIP helipad (pavement, lighting, lounge). At the end of Phase 3, the resort achieves full operational capacity and the soft-opening of the hotel is scheduled for Month 46.

8.5 Phase 4: Museum, Theme Park & Final Landscaping (Months 48–60)

Phase 4 is the completion phase, during which the heritage and experiential components are delivered and the resort achieves its final operational form. The deliverables are: (1) the expanded Tea Museum interpretive centre (galleries, interpretation, retail), (2) the theme park and open party centre (family recreation zone), (3) the boundary wall commercial shops (tea souvenir and local artisan retail), (4) the final landscaping and botanical garden Phase 2 planting, (5) the golf course grow-in and final turf establishment, and (6) the staff training and operational commissioning for all departments. The grand opening of the resort is scheduled for Month 60, with a phased ramp-up to full occupancy over the following 12 months.

8.6 Phase Summary Table

Phase	Timeline	Scope	Indicative Cost	Gating Criteria
Phase 1	Months 1–9	Survey, design, approvals, financial close	USD 5–8 M	BTB in-principle approval; lender term sheets
Phase 2	Months 9–24	Entrance, infrastructure, 45 cottages, mosque, Lake 1	USD 30–45 M	Phase 1 financial close; EIA clearance
Phase 3	Months 24–48	Hotel, golf, cable car, helipad, 65 more cottages, Lake 2	USD 60–90 M	Phase 2 revenue generation; lender disbursement schedule
Phase 4	Months 48–60	Museum expansion, theme park, shops, final landscape, soft opening	USD 15–22 M	Phase 3 hotel structural completion; staff recruitment underway
Total	60 months	Full resort operational	USD 110–165 M	All phases gated by Steering Committee approval

Table 8.1 — Implementation phase summary with indicative costs (subject to verified BOQ).

CHAPTER 09

Investment Framework & Financial Model

The indicative investment envelope, partnership structure, revenue model, and concession framework — all subject to verification through detailed feasibility.

9.1 Indicative Investment Envelope

The total indicative investment for the project is estimated at BDT 1,200–1,800 crore (approximately USD 110–165 million) over the 60-month construction period. This estimate is derived from the concept master plan and international benchmark costs for comparable eco-luxury resort developments in South Asia. It must be emphasised that this is an indicative range only; the final budget will be established through a verified Bill of Quantities (BOQ) based on detailed engineering design, current market rates, and competitive procurement. No total budget figure will be presented as final until the BOQ is verified and tendered.

9.2 Investment Breakdown by Category

Category	Scope	BDT Crore	Basis / Notes
Civil Construction — Cottages	110 eco-luxury & duplex cottages, including foundations, structure, fit-out, decks	30–45	Bangladesh cottage construction benchmarks; timber + stone cladding premium
Civil Construction — Hotel	150-room 5-star hotel, including structure, fit-out, FF&E;, IT	40–60	International 5-star hotel benchmark; USD 270K–400K per key
Civil Construction — Mosque	Eco-heritage mosque, 200–300 musalli capacity	1–2	Specialist biophilic design; stone + timber materials
Civil Construction — Museum Expansion	Tea Museum interpretive centre expansion and galleries	3–5	Heritage-grade fit-out; interpretive technology
Infrastructure — Roads, Drainage, Utilities	Internal roads, eco-pedestrian network, drainage, water, electricity, sewage	8–12	Hill-terrain premium; eco-drainage requirements
Landscaping & Outdoor Development	Twin lakes, botanical gardens, timber promenades, planting	6–10	Lake excavation; mature-tree transplanting; arboretum
Special Facility — Cable Car	0.5 km mono-cable detachable gondola system	6–10	International supplier; subject to separate technical survey
Special Facility — Golf Course	9-hole course, irrigation, clubhouse, turf establishment	5–8	Championship-feel design; rainwater irrigation

Category	Scope	BDT Crore	Basis / Notes
Special Facility — Helipad	ICAO-compliant helipad, lounge, access road	1–2	Pavement, lighting, ICAO certification
Soft Costs — Design, PM, Approvals	Architectural, engineering, project management, approvals, EIA	8–12	8–10% of construction cost (international standard)
Contingency & Financing	10% contingency; financing costs during construction	12–18	Standard project contingency; lender requirements
Total Indicative	**All categories combined**	**120–180**	**Subject to verified BOQ and market rates**

Table 9.1 — Indicative investment breakdown by category (subject to verified BOQ).

9.3 Partnership & Concession Structure

The project is proposed to be developed through a Public-Private Partnership (PPP) or Joint Venture (JV) framework between the Bangladesh Tea Board (BTB) and Blue Mirror Project Group. Under the proposed structure, BTB contributes the 26-acre land asset (at agreed valuation) and retains ownership throughout the concession period; Blue Mirror Project Group contributes the entire capital investment, the development expertise, and the operating capability. A Special Purpose Vehicle (SPV) is established to hold the concession, with BTB and Blue Mirror holding equity in proportion to their respective contributions. The SPV receives all operating revenue, pays operating expenses, services debt, and distributes the surplus to the partners according to an agreed profit-sharing formula.

The proposed concession period is 30 years from the date of commercial operation, with the option for a 10-year extension subject to performance review. During the concession period, BTB receives (a) a fixed annual concession fee (payable quarterly), (b) a revenue-share of 10–15% of gross operating revenue, and (c) a profit-share of 15–25% of net operating profit. At the end of the concession period, all built assets revert to BTB at no cost, in good operating condition, with a fully trained Bangladeshi operating team in place. The detailed financial terms will be established through a transparent competitive procurement process supervised by an independent transaction advisor.

9.4 Revenue Model

The resort generates revenue from five principal streams, providing diversified income that is resilient to seasonality and demand fluctuations. The revenue mix has been benchmarked against comparable international eco-luxury tea-heritage resorts in India, Sri Lanka, and Nepal, with adjustments for the specific market context of Bangladesh.

Revenue Stream	Scope	Share	Notes / Targets
Room Revenue	Cottages + Hotel rooms	55%	Year-3 ADR target: USD 180–250; occupancy 60%+

Revenue Stream	Scope	Share	Notes / Targets
Food & Beverage	Restaurants, bars, tea-pairing, banqueting	20%	High-margin; tea-pairing as signature experience
Spa & Wellness	Treatments, fitness, wellness packages	8%	Premium pricing; international therapist team
Golf & Recreation	Green fees, cart hire, pro-shop, cable car, lake activities	10%	Year-round; cable car as paid attraction for day visitors
Convention & Events	Hall rental, corporate retreats, weddings	7%	Off-peak demand driver; high margin

Table 9.2 — Revenue model with indicative stream mix.

9.5 Operating Cost Structure

Operating costs are projected at approximately 45–55% of gross revenue, in line with international five-star resort benchmarks. The principal cost categories are: (1) rooms department (linen, amenities, cleaning, reservation), (2) F&B; department (food cost at 25–30% of F&B; revenue, kitchen labour), (3) spa & wellness (therapist labour, products), (4) golf & recreation (course maintenance, equipment), (5) sales & marketing (including international representation), (6) administration & IT, (7) energy & utilities, (8) maintenance & repair, and (9) property tax & insurance. Detailed operating cost projections will be developed in the feasibility phase using bottom-up estimates for each department.

9.6 Financing Structure

The proposed financing structure is a 60:40 debt:equity ratio, in line with international infrastructure and hospitality project finance norms. The debt component (approximately USD 65–100 million) is expected to be sourced from a syndicate of Bangladesh commercial banks (with possible participation from international development finance institutions such as IFC, ADB, or AIIB), secured against the project assets and supported by a revenue intercept account. The equity component (approximately USD 45–65 million) is contributed by Blue Mirror Project Group and any co-investors identified during the financial close process. The financing structure will be finalised based on the detailed feasibility study and the lender due diligence process.

CHAPTER 10

Risk Management & Governance Framework

The risk register, mitigation strategies, and governance architecture that protect both the Bangladesh Tea Board and the private partner throughout the project lifecycle.

10.1 Risk Register

The project faces a structured set of risks across environmental, construction, financial, regulatory, operational, and commercial categories. The risk register below identifies the principal risks, assesses their likelihood and impact, and defines mitigation strategies for each. The register will be maintained as a live document throughout the project lifecycle, with quarterly review by the Steering Committee and annual independent audit.

Category	Risk	Likelihood	Impact	Mitigation
Environmental	Disturbance to tea-ridge ecology during construction	Medium	High	Zero tree-cutting policy; protected root zones; ecological supervisor on-site; EIA-driven mitigation
Environmental	Soil erosion from hill-terrain earthworks	Medium	Medium	Phased excavation; bio-engineering; silt fences; monsoon-season work restriction
Construction	Hill-terrain geotechnical surprises (rock, soft soil)	Medium	Medium	Detailed geotechnical investigation in Phase 1; design contingency; flexible foundation system
Construction	Weather delays during monsoon (May–September)	High	Medium	Seasonal work planning; weather-protected work areas; float in schedule
Financial	Cost overrun beyond contingency	Medium	High	10% contingency; fixed-price contracts; independent quantity surveyor; phased disbursement
Financial	Foreign exchange exposure on imported equipment	Medium	Medium	Hedging strategy; local sourcing priority; FX clause in contracts
Regulatory	Delay in BTB / MOCA / DOE approvals	Medium	High	Early engagement; concurrent approval processing; Steering Committee escalation
Regulatory	PPP/JV framework agreement negotiation delay	Medium	High	Independent transaction advisor; precedent PPP structures; Ministry of Commerce engagement

Category	Risk	Likelihood	Impact	Mitigation
Operational	Hospitality talent shortage in Sreemangal	High	Medium	Pre-opening training academy; partnership with hospitality institutes; international trainer team
Operational	Service-quality shortfall vs international 5-star	Medium	High	International operator partnership; monthly guest satisfaction tracking; ISO certification
Commercial	Lower-than-projected demand in ramp-up years	Medium	High	Conservative ramp-up assumptions; multi-segment demand strategy; BTB revenue-floor protection
Commercial	Competitive new resort entry in Sreemangal	Low	Medium	First-mover advantage; heritage differentiation; long-term BTB partnership

Table 10.1 — Project risk register with mitigation strategies.

10.2 Governance Architecture

The project is governed through a three-tier architecture designed to balance the strategic interests of BTB with the operational autonomy required by the private partner. The three tiers are: (1) the Steering Committee (strategic oversight), (2) the Project Management Office (execution), and (3) the Independent Review Panel (assurance). Each tier has defined composition, responsibilities, and decision rights, with explicit escalation paths to ensure that disputes are resolved efficiently and the project schedule is protected.

10.3 Steering Committee

The Steering Committee is the apex governance body, comprising: (1) the Chairman of BTB or nominee (Committee Chair), (2) a Joint Secretary from the Ministry of Commerce, (3) a representative of the Ministry of Civil Aviation & Tourism, (4) the Managing Director of Blue Mirror Project Group, (5) an independent environmental expert nominated by the Department of Environment, and (6) an independent hospitality expert nominated by the Bangladesh Tourism Board. The Committee meets quarterly during the construction phase and semi-annually during the operations phase, with extraordinary meetings convened to address escalation items. The Committee approves phase gates, annual budgets, major variations, and the appointment of the Independent Review Panel.

10.4 Independent Review Panel

The Independent Review Panel is a three-member panel of independent experts, appointed by the Steering Committee, providing assurance on technical, environmental, and financial matters. The Panel comprises: (1) a chartered engineer with international hospitality experience, (2) an environmental scientist with tea-ecosystem expertise, and (3) a chartered accountant with project finance experience. The Panel reviews and reports on: (a) the annual environmental audit, (b) the annual financial audit, (c) the construction quality audit at each phase gate, and (d) any matter referred to it by the Steering Committee. The Panel's reports are

submitted simultaneously to the Steering Committee and to the Ministry of Commerce, ensuring transparency.

10.5 Contract & Procurement Framework

All procurement above a threshold value (proposed: BDT 5 crore) is conducted through open competitive tender, supervised by an independent procurement consultant appointed by the Steering Committee. All contracts use international standard forms (FIDIC for construction, NEC for engineering) adapted for Bangladesh legal context. A contract management unit within the PMO tracks contract performance, variations, claims, and disputes. Disputes are resolved through a tiered process: (1) PMO-level negotiation, (2) Steering Committee mediation, (3) expert determination by an independent expert, and (4) arbitration under the Bangladesh International Arbitration Centre (BIAC) rules. The framework is designed to ensure that disputes do not delay the project schedule while protecting the legitimate interests of all parties.

CHAPTER 11

Expected Outcomes & Socio-Economic Impact

The quantified economic, social, environmental, and brand outcomes that the project will deliver for the Bangladesh Tea Board, the local community, and the national tourism economy.

11.1 Employment Generation

The project is expected to create approximately 800–1,200 direct jobs across the construction phase (60 months) and the operations phase (30 years), with a further 1,500–2,000 indirect jobs generated through the supply chain, transport, artisan, and ancillary services. Direct operational employment will span hospitality (rooms, F&B;, spa, golf), engineering (maintenance, utilities), horticulture (landscaping, tea ridges, golf course), heritage (museum curators, interpretive guides), and administration (finance, HR, IT, sales & marketing). At least 60% of operational staff will be recruited from the local Sreemangal and tea-garden labour community, with a structured 12-month pre-opening training programme and clearly defined career-progression pathways to international five-star standards.

DIRECT JOBS	INDIRECT JOBS	LOCAL RECRUITMENT	TRAINING PROGRAMME
800–1,200	**1,500–2,000**	**60%+**	**12 months**
Construction + operations across all departments	Supply chain, transport, artisan, ancillary	From Sreemangal and tea-garden labour community	Pre-opening hospitality skills academy

11.2 Tourism Development Impact

The project will position Sreemangal as a flagship destination on the international tea-tourism map, generating measurable uplift across the local tourism economy. The resort is projected to attract 150,000+ annual visitors by Year 5 (compared to the current ~25,000 visitors per year to the existing BTB resort), of which approximately 40% are expected to be foreign tourists and the Bangladeshi diaspora. The average length of stay is projected to increase from the current 1.2 nights to 2.8 nights, driven by the diversity of on-site attractions (cable car, golf, museum, lakes) and the experiential depth of the heritage programming. This uplift will directly benefit the broader Sreemangal tourism ecosystem, including local restaurants, transport operators, tea-garden tour operators, and the Lawachara National Park visitor flow.

11.3 Foreign Exchange Earnings

The resort is projected to generate approximately USD 8–12 million per annum in foreign exchange earnings by Year 5, through foreign tourist accommodation, F&B;, and ancillary spend. This figure is based on the projected 60,000 foreign-tourist guest nights per year (40% of 150,000 visitors × 1-night average for day visitors, 2.8 nights for overnight guests) at an average per-guest spend of USD 220–280 (room + F&B; + activities). These earnings contribute directly to Bangladesh's balance of payments and support the national

objective of growing the tourism sector's share of GDP from the current 4% to the targeted 6% by 2030.

11.4 Local Business Development

The project is committed to a local procurement target of 40% of operating supplies (excluding imported FF&E; and specialty equipment), channelling approximately BDT 15–25 crore per annum into the local Sreemangal economy by Year 5. Local procurement categories include: (1) fresh produce and dairy from Sreemangal and Moulvibazar farmers, (2) fish from local fisheries for the lakes and F&B;, (3) tea from BTB and local gardens for retail and F&B;, (4) handicrafts from local artisans for retail and room amenities, (5) transport services for guest transfers and tours, (6) landscaping supplies (plants, mulch, soil), and (7) maintenance services (cleaning, security, pest control). The local procurement programme will be supported by a dedicated local-supplier development officer within the resort procurement team.

11.5 Outcomes Summary

Outcome Indicator	Baseline (Today)	Year-5 Target	Timeline
Direct Employment	~30 (current BTB resort staff)	1,000+ across all departments	Year 5
Indirect Employment	Limited	1,500–2,000 in supply chain and ancillary	Year 5
Annual Visitors	~25,000 (current)	150,000+ (40% foreign)	Year 5
Average Length of Stay	1.2 nights (current)	2.8 nights	Year 5
Foreign Exchange Earnings	Negligible	USD 8–12 million per annum	Year 5
Local Procurement Spend	Limited	BDT 15–25 crore per annum	Year 5
Annual BTB Concession Income	Limited (cottage revenue)	BDT 80–120 crore per annum	Year 5
International Certifications	0	3+ (ISO 14001, Green Key, LEED equivalent)	Year 5
Tree Cover Index	100 (baseline)	115+ (net positive after replanting)	Year 5
Bangladesh Tea Brand Visibility	Regional	International (top-3 South Asian tea-heritage resorts)	Year 5

Table 11.1 — Summary of expected outcomes with baseline and Year-5 targets.

11.6 Alignment with National Goals

The project aligns directly with several stated national goals of the Government of Bangladesh: (1) the Bangladesh Tourism Master Plan's objective of diversifying tourism offerings beyond Cox's Bazar and Sundarbans, (2) the National Tourism Policy's target of growing tourism's share of GDP to 6% by 2030, (3)

the Bangladesh Tea Board's strategic mandate to diversify the use of tea-sector land for high-value complementary activities, (4) the government's commitment to attracting foreign direct investment in infrastructure and hospitality, and (5) the Sustainable Development Goals (particularly SDG 8 Decent Work, SDG 11 Sustainable Cities, SDG 12 Responsible Consumption, SDG 15 Life on Land). The project's success would establish a replicable model for BTB-led tourism development across the other tea-growing regions of Bangladesh.

CHAPTER 12

Conclusion & Request for Approval

A summary of the proposal and the specific approvals requested from the Bangladesh Tea Board.

12.1 Summary of the Proposal

This Master Project Proposal presents a comprehensive concept master plan for the transformation of the Bangladesh Tea Board's 26-acre property at Sreemangal into an international five-star eco-luxury tea-heritage resort, integrated with a 9-hole golf course, a 0.5-kilometre cable car, a VIP helipad, twin lakes, an eco-heritage mosque, an expanded Tea Museum, and 110 eco-luxury cottages alongside a 150-room iconic hotel. The proposal is grounded in the verified source materials — the BTB Tea Resort & Museum profile dossier and the interactive project presentation hosted at bluemirror.24bd7.com — and is structured to deliver measurable economic, social, environmental, and brand returns for the Bangladesh Tea Board, the local community of Sreemangal, and the national tourism economy.

The proposed development philosophy is rooted in three non-negotiable principles: (1) 100% preservation of the heritage artefacts and the virgin tea ridges, (2) net-positive environmental impact through tree replanting, rainwater harvesting, and renewable energy, and (3) inclusive local employment with structured training and career-progression pathways. The proposed investment of BDT 1,200–1,800 crore (USD 110–165 million) over a 60-month phased implementation is structured as a Public-Private Partnership between BTB (as land-owner) and Blue Mirror Project Group (as developer-operator), with BTB retaining ownership of the land and receiving a recurring concession fee plus revenue and profit share throughout the 30-year concession period.

12.2 Strategic Case

The strategic case for the project rests on five pillars: (1) the exceptional heritage value of the property as the oldest existing tea-heritage site in Bangladesh with continuous institutional custodianship since the 1840s; (2) the alignment with the Bangladesh Tourism Master Plan, the National Tourism Policy, and the strategic mandate of the Bangladesh Tea Board; (3) the demonstrated international demand for premium tea-heritage tourism, evidenced by the performance of comparable properties in Darjeeling, Sri Lanka, and Nepal; (4) the opportunity to position Bangladesh on the international tea-tourism map and generate measurable foreign exchange earnings; and (5) the inclusive development impact through local employment, local procurement, and skills development. The project represents a unique opportunity to convert an under-utilised BTB asset into a flagship international destination that benefits all stakeholders.

12.3 Specific Approvals Requested

Blue Mirror Project Group respectfully requests the following specific approvals from the Bangladesh Tea Board to enable the project to proceed to the detailed feasibility phase:

- **In-principle approval** of the concept master plan and the 26-acre land utilisation pattern described in Chapter 5 of this proposal.
- **Authorisation to conduct a detailed feasibility study**, including topographical survey, geotechnical investigation, Environmental Impact Assessment, market demand analysis, and detailed financial modelling, at the cost of Blue Mirror Project Group.
- **Formation of a joint technical committee** comprising representatives of BTB, the Ministry of Civil Aviation & Tourism, the Department of Environment, and Blue Mirror Project Group, to oversee the feasibility phase and report to the Steering Committee.
- **Approval in principle to negotiate a PPP/JV framework agreement**, setting out the governance, revenue-sharing, concession period, and exit provisions for both parties, with the appointment of an independent transaction advisor to support the negotiation.
- **Allocation of development rights** to Blue Mirror Project Group for an initial 30-year concession period (renewable for a further 10 years subject to performance review), conditional on the successful completion of the detailed feasibility study and the negotiation of the PPP/JV agreement.
- **Authorisation to commence stakeholder engagement** with the Ministry of Commerce, the Ministry of Civil Aviation & Tourism, the Department of Environment, the Civil Aviation Authority of Bangladesh (for the helipad), the local Sreemangal administration, and the local community, to ensure that all prerequisites for the detailed feasibility phase are in place.

12.4 Closing Commitment

Commitment from Blue Mirror Project Group

Blue Mirror Project Group is fully committed to the long-term success of this project and to a partnership with the Bangladesh Tea Board that respects the heritage, ecological, and social value of the Sreemangal property. We undertake to conduct the detailed feasibility study with full transparency, to engage all stakeholders with respect and good faith, to deliver every phase of the project to international standards, and to operate the resort in a manner that brings credit to the Bangladesh Tea Board and to Bangladesh. We look forward to the opportunity to work with the Bangladesh Tea Board to make this vision a reality.

CHAPTER 13

Annexures

Supporting technical specifications, source material references, and contact information.

Annexure A — Detailed Land Balance Sheet

The complete land balance sheet for the 26-acre property, organised by zone, with acreage, decimal, and bigha measurements.

#	Zone	Acres	Decimals	Bigha	Notes
1	Eco-Luxury & Duplex Cottages	6.81	681.0	20.6	80 single-story + 30 duplex
2	5-Star U/L-Shaped Hotel Complex	3.66	366.0	11.1	150 rooms + commercial
3	Mega Lake & Floral Arboretum	3.30	330.0	10.0	Twin lakes 200m × 30m
4	Cable Car Transit System	0.57	57.4	1.74	0.5 km ridge-to-ridge
5	Eco-Heritage Mosque	0.28	28.0	0.85	200–300 musalli
6	VIP Helipad	0.34	34.4	1.04	ICAO-compliant
	Total Built Infrastructure	14.96	1,496.8	45.33	57.5% of property
7	Conserved Tea Ridges & Green Buffer	11.04	1,103.2	33.37	42.5% of property
	Grand Total	26.00	2,600.0	78.70	100% BTB-owned

Table A.1 — Detailed land balance sheet.

Annexure B — Helipad Technical Specifications

- **Compliance Standard:** ICAO Annex 14, Volume II (Heliports)
- **TLOF (Touchdown and Lift-Off) Zone:** Reinforced Cement Concrete (RCC) pavement, designed for Bell 412, Eurocopter EC155, and Augusta Westland AW139 helicopter classes
- **FATO (Final Approach and Take-Off) Zone:** Obstacle-free approach and take-off flight path, aligned with prevailing wind direction
- **Pavement Load Capacity:** Minimum 12 tonnes single-wheel load; 18 tonnes dual-wheel load
- **Lighting:** Omni-directional perimeter lights (FATO edge); floodlighting for TLOF; wind direction indicator (lit windsock)
- **Approach Path:** Clear of all built infrastructure; protected by BTB-approved zoning around the helipad

- **VIP Access Road:** Dedicated bitumen-surfaced road from helipad to hotel reception, approximately 350 metres, with landscaped pedestrian trail and security control point
- **Waiting Lounge:** 80 m^2 lounge with VIP drop-off, refreshment area, and security screening
- **Regulatory Approvals:** Civil Aviation Authority of Bangladesh (CAAB) licensing required; separate environmental clearance from Department of Environment

Annexure C — Cable Car System Parameters

- **System Type:** Mono-cable detachable gondola (MDG)
- **Route Length:** Approximately 0.5 kilometres, ridge-to-ridge
- **Vertical Rise:** Approximately 35–45 metres (subject to detailed survey)
- **Cabin Capacity:** 8 passengers per cabin
- **Line Speed:** 0–5 metres per second (variable)
- **Theoretical Capacity:** 600 passengers per hour per direction
- **Stations:** 2 stations — East Station (integrated with hotel/cottage zone), West Station (integrated with golf course and cable car ridge cottages)
- **Power Supply:** Grid-connected primary, diesel generator backup
- **Safety Systems:** Anti-rollback device, emergency brake, evacuation kit, cabin communication, weather monitoring
- **Operating Hours:** 7:00 AM – 9:00 PM daily, weather permitting
- **Supplier Selection:** International competitive tender; expected suppliers include Doppelmayr, Leitner, or POMA

Annexure D — Museum Heritage Artefact Categories

The Tea Museum's existing collection, categorised for the proposed expanded interpretive programme:

Artefact Category	Period	Interpretive Treatment
Mechanical Rollers	Colonial-era	Functional exhibit with interpretation
Leaf Sorters	Colonial-era	Interactive demonstration
Weight Measures	19th century British	Static exhibit with context panels
Soil Test Apparatus	BTRI historical	Interpretive display with modern comparison
Surveillance Lamps	Colonial-era	Atmospheric exhibit with lighting design
Tea Coins & Tokens	19th – early 20th century	Numismatic display with social-history context
Brass Water Vessels	Traditional	Material-culture exhibit

Artefact Category	Period	Interpretive Treatment
Pruning Shears	Pre-mechanisation	Comparative display with modern equipment

Table D.1 — Museum artefact interpretive treatment matrix.

Annexure E — Source Materials Reference

This proposal has been developed from the following verified source materials:

- **Source 1 (PDF):** BTB Tea Resort & Museum Profile Dossier — the official project profile document of the Bangladesh Tea Board for the Sreemangal property, covering heritage context, existing infrastructure, proposed development zones, architectural concepts, and land balance sheet.
- **Source 2 (Website):** Interactive project presentation hosted at https://bluemirror.24bd7.com/ — a 25-slide interactive presentation covering all components of the proposed master plan, including project overview, executive summary, main gate, museum area, theme park, boundary wall, cable car, 9-hole golf course, 150-room hotel, cottages, accommodation, dining, swimming pool, waterway, cable car plan, tea garden, museum heritage, recreation, infrastructure, environmental plan, implementation roadmap, indicative budget, financial model, expected outcomes, and conclusion.
- **Both source materials** have been archived in this proposal's companion GitHub repository (https://github.com/kifayat1386/resort) under the *source-data/* directory, with the original PDF in *source-data/pdf/* and the scraped website content (HTML, JSON, transcript, and all image assets) in *source-data/website/*.

Annexure F — Contact Information

Field	Value	Notes
Submitted By	Blue Mirror Project Group	Master Developer & Operator
Submitted To	Chairman, Bangladesh Tea Board	Project Owner & Custodian
Project Location	Sreemangal, Moulvibazar, Bangladesh	26-acre BTB property
Document Version	v1.0 — Concept Master Plan	Subject to detailed feasibility
Submission Date	October 2026	For official review by BTB
Companion Repository	github.com/kifayat1386/resort	Source materials archive

Table F.1 — Proposal contact and reference information.